# CMOS CAMERA MODULES


your BEST camera module partner

## KLT-IRSW-OS02C10 V1.0

### OmniVision OS02C10 with IR Switch MIPI インターフェース 固定焦点 2MP M12 カメラモジュール




| カメラモジュール番号 | KLT-IRSW-OS02C10 V1.0    |                            |
|------------|--------------------------|----------------------------|
| イメージセンサー   | OS02C10                  | IR SWITCH                  |
| EFL        | 1.07 mm                  | Input Voltage: 3.3V ~ 5.5V |
| F.NO       | 2.0                      | IR: 645nm +/- 15nm         |
| ピクセル       | 1920 x 1080              | AR: 700nm ~ 1000 nm        |
| 視野角        | 210°(D) 210°(H) 210°(V)  | Operation (IR Day Time)    |
| レンズタイプ     | 1/2.8 インチ                | Red Line: Negative         |
| レンズ寸法      | 24.80 x 16.00 x 15.66 mm | Black Line: Positive       |
| モジュールサイズ   | 57.07 x 30.00 mm         | Operation (AR Night Time)  |
| モジュールのタイプ  | 固定焦点                     | Red Line: Positive         |
| インターフェース   | MIPI                     | Black Line: Negative       |



www.KaiLapTech.com sales@KaiLapTech.com Tel: (852) 6908 1256 Fax: (852) 3017 6778

All rights reserved @ Kai Lap Technologies Group Ltd. Specifications subject to change without notice.



# OSO2C10 2-megapixel product brief



lead free available in a lead-free package

# Image Sensor Combines Ultra Low Light and Nyxel<sup>™</sup> NIR Technologies for Industry's Best Nighttime Camera Performance

OmniVision's OSO2C10 is a 2.9-micron, 2-megapixel image sensor with breakthrough ultra-low-light (ULL) technology. Combining ULL with OmniVision's industry-leading Nyxel<sup>™</sup> near-infrared (NIR) technology, the OSO2C10 works equally well in all lighting conditions. It can detect incident light in both visible and NIR wavelengths and produce precise color and monochrome images for security applications such as remote surveillance cameras with Al for accurate facial recognition.

Nyxel NIR technology infuses the OSO2C10 with exceptional quantum efficiency (QE) of 60% at 850 nm and 40% at 940 nm, which is 2x to 4x better than competing devices. This enables the use of lower-power IR illumination in total darkness, resulting in an estimated 3x reduction in system-level power consumption. Additionally, 940 nm NIR lighting cannot be detected by the human eye in dark indoor settings, while 850 nm light is ideal for outdoor security cameras. The OS02C10's ability to capture crisp, clear images using undetectable 940 nm NIR light means that indoor security cameras will not disturb sleeping occupants, and can be easily concealed from intruders.

The amount of NIR light that a sensor requires to capture high-quality images can be quantified with a new metric called NIR SNR1, which takes into account the QE, pixel size and read noise. The OCO2C10 achieves an SNR1<sub>850nm</sub> of 23nW/cm<sup>2</sup> and an SNR1<sub>940nm</sub> of 31nW/cm<sup>2</sup>, which means designers can reduce IR illumination to consume 2x to 4x less power compared to the competitors' sensors, for the same environment and over the same image-detection range.

The OCO2C10 has a superior low-noise design, achieving an SNR1 of 0.16 lux while producing high definition 1080p images. OmniVision's proprietary dual-conversion-gain technology allows this sensor to achieve the industry's best ULL performance, while the 3-frame staggered shutter minimizes motion artifacts and enables a high dynamic range (HDR) of 120 dB. Additionally, these technologies are easily upgradable to 2K and 4K resolution as security systems begin their transition to higher-quality displays.

Find out more at www.ovt.com.





#### Applications

- Security Camera
- Action Camera
- High Resolution Consumer Camera

#### **Product Features**

- QE enhancement in NIR range
- support for image size: 1920 x 1080 - VGA - QVGA, and any cropped size
- high dynamic range
- high sensitivity
- programmable conversion gain
- image sensor processor functions:
  defective pixel cancelation automatic black level correction, etc.

- pixel data: 12b RAW RGB
- SCCB for register programming
- programmable GPIOs
- high speed serial data transfer with MIPI CSI-2 or LVDS
- external frame synchronization

- capability
- embedded temperature sensor
- one time programmable (OTP) memory

#### OS02C10-J70A-Z (color, lead-free) 70-pin fan-out package

### **Product Specifications**


- active array size: 1920 × 1080
- power supply:
  - analog: 2.8V digital: 1.1V I/O pins: 1.8V
- temperature range:
  operating: -30°C to +85°C junction temperature
- output interfaces: up to 4-lane MIPI CSI-2 or LVDS
- input clock frequency: 6 36 MHz
- lens size: 1/2.8"
- lens chief ray angle: 9° linear
- SCCB speed: up to 1 MHz
- scan mode: progressive
- shutter: rolling shutter

 output formats: linear output, dual exposure HDR (long and short), 3-exposure HDR (long, short, and very short), conversion gain programmable in each channel

OS02C10

- maximum image transfer rate:
  40X3 fps @ 1080p in 10-bit
  30X3 fps @ 1080p in 12-bit
- sensitivity: 32,000 e<sup>-</sup>/Lux-sec (green pixel response at 530 nm illumination)
- dynamic range: >120 dB 3-exposure staggered HDR
- **pixel size:** 2.9 μm x 2.9 μm
- **image area:** 5614.4 μm x 3178.4 μm
- package dimensions: fan-out: 8903 µm x 7100 µm

#### Functional Block Diagram





Version 1.2, October, 2018